

# 数 量 表

古町学校道線(補助分)

種 別	名 称	規格・寸法	単位	数量	摘 要
土工	掘削				
	C1		m3	78.2	
	盛土				
	B1		m3	7.2	
	法面整形				
	L1		m2	134.2	
	残土運搬				
	L=2.5km以下	$(78.2+45.7)-(7.2+19.8)/0.9=93.9$	m3	93.9	
	残土処理場整地				
			m3	93.9	
作業土工	床掘				
	C2		m3	45.7	
	埋戻し				
	B2		m3	19.8	
	基面整正				
	W1	$0.65 \times 38.6m = 25.1$	m2	25.1	
擁壁工	コンクリートブロック積				
	1:0.5		m2	128.9	
	天端コンクリート				
	18-8-25BB	$(0.69/10m) \times 38.6 = 2.66$	m3	2.66	
	基礎コンクリート				
	18-8-40BB		m	38.6	
	裏込コンクリート				
	18-8-25BB		m3	19.33	
	裏込材				
	RC-40		m3	34.8	
	水抜きパイプ				
	Φ50 L=500		箇所	65	
	目地材				
	t=10		m2	14.8	
	小口止	Con:0.43			
	W=300	型枠:3.4	式	1	
舗装工	下層路盤				
	クラッシャーラン C-25 t=10cm		m2	31.1	
	上層路盤				
	粒調碎石 M-25 t=10cm		m2	31.1	



# 土工数量計算書

測 点	距 離	掘 削 C1			床 掘 C2			盛 土 B1			埋 戻 し B2			法 面 整 形 L1			備 考
		面 積	平 均	体 積	面 積	平 均	体 積	面 積	平 均	体 積	面 積	平 均	体 積	長 さ	平 均	面 積	
0.0																	
9.4																	
21.0																	
27.5	6.5	0.2															
31.0	3.5	0.2	0.20	0.7													
36.0	5.0	0.2	0.20	1.0													
46.7	10.7	1.5	0.85	9.1	1.2			1.0			0.5			2.9			
57.3	10.6	3.0	2.25	23.9	1.2	1.20	12.7	0.0	0.50	5.3	0.5	0.50	5.3	5.0	3.95	41.9	
62.9	5.6	1.9	2.45	13.7	1.2	1.20	6.7	0.2	0.10	0.6	0.5	0.50	2.8	3.8	4.40	24.6	
76.3	13.4	1.3	1.60	21.4	1.1	1.15	15.4	0.0	0.10	1.3	0.5	0.50	6.7	2.9	3.35	44.9	
86.2	9.9	0.4	0.85	8.4	1.1	1.10	10.9				0.5	0.50	5.0	1.7	2.30	22.8	
合 計	65.2			78.2			45.7			7.2			19.8			134.2	

